MUSKEG LAKE CREE NATION 102

P.O. Box 248

Marcelin, Saskatchewan

S0J 1R0

Telephone: 306 466-4959
Facsimile: 306 466-4951

Scope of work

House 423 Bruce Arcand Renovation
1070 Sq ft Bungalow

- All carpentry, heating, plumbing, and electrical finishes to be completed as required. Workmanship shall be carried out in accordance with industry standards and good construction practices.
- **Work to include all demolition and disposal of materials to suitable landfill site**.
- All permits and inspection reports to be obtained as per local authority having jurisdiction.
- Dimensions and quantities provided on this list of work items shall be considered approximate. The contractor is responsible for confirming all dimensions and quantities on site.

1. **General:**
   Provide all the labor, tools, equipment and supervision to complete the work, including but not limited to the supply and installation of all rough and finish, carpentry, millwork, doors, windows, glass, hardware, insulation, trim, flooring and mechanical required for the proper construction and completion of the work and for temporary services and maintenance of the work site during construction.
   The construction must meet the current editions of the National Building Code of Canada, other applicable building codes and all applicable CSA standards.
2. **Remove & replace flooring**
   Install new flooring 5.3mm VPF

Material Cost $_____ Labor Cost $_____

3. **Remove & Replace Exterior Doors**

   Material Cost $_____ Labor Cost $_____

4. **Remove & Install new Kitchen Cabinets**

   Material Cost $_____ Labor Cost $_____

5. **Electrical inspection**
   Check all switches, plugs, cover plates, check panel and breakers and wiring throughout, replace outside plugs with new GFIC weather protected if needed, provide J Form. Hanging plug in basement

   Sub-Trades
   Electrical Cost $ MLCN Plumbing Cost $ MLCN

6. Garbage bin & tipping fee $_____

If an item is not quoted when the bids are reviewed the bid becomes incomplete, an incomplete bid will result in the bid being null and void. Please insure every item is quoted on in bid.

Name_____

Phone Number_____